





ARCOSA Inc. (TRINITY STRUCTURAL TOWERS)

Newton, Iowa

DELIVERY IN 2018

Blastman B12 robot



OBJECTIVE

Automate blast cleaning
Improve health and safety
Improve quality and efficiency of blast cleaning

PROCESS INFORMATION

Workpiece

- Wind tower sections/frames

Workpiece condition

-New production, rust grade A

Pressure

- 8-10 bar

Abrasive

- Steel grit

Nozzle / robot

- 2 x 19 mm

Efficiency

 $-150 - 250 \text{ m}^2/\text{h}$

Typical manual blasting efficiency

- 15-20 m²/h/person

Cleanliness

- Sa 2,5